



Welcome!

Microwave 101

Microwave 101 Webinar Series

PRESENTER



Greg Macey
Manager, Microwave

REGISTER:

www.comsearch.com/microwave-101/

DAY 1: **Microwave Fundamentals Part I** (May 23)

- Microwave Components
- RF Propagation
- Field Survey
- 6 GHz Microwave Assurance

DAY 2: **Microwave Fundamentals Part II** (June 27)

- Path Reliability
- Path Design Considerations
- iQ.link — Microwave Design Software (Live Demo)

DAY 3: **Understanding the Frequency Coordination Process** (July 25)

- Interference Analysis
 - o Microwave
 - o Earth Station
- Frequency Planning & Protection
- FCC Licensing & Management
- Comsearch Connect - Customer Portal
- FCC Regulatory Updates (6 GHz, 80 GHz, 13 GHz)

Understanding the Frequency Coordination Process

1. Interference Analysis




Greg Macey

Manager, Microwave


Why do you need an interference analysis?

Los Angeles (50-mile radius):
6, 11, 18 & 23 GHz




MICROWAVE PATH COUNTS BY BAND


Number of MW Paths in U.S. (April 2023)





MICROWAVE PATHS IN THE U.S. — 6 GHZ BAND



MICROWAVE PATHS IN THE U.S. — 11 GHZ BAND




MICROWAVE PATHS IN THE U.S. — 18 & 23 GHZ BAND




E-BAND (71-76 / 81-86 GHZ) LINK REGISTRATION GROWTH


New E-Band Link Registrations by Year



E-Band Cumulative Total Registered Links




INTERFERENCE ANALYSIS | SOURCES



C/I → The ratio of desired signal power to interference power at the receiver

$$C/I = C(\text{dBm}) - I(\text{dBm})$$




The interference path from **Site D to Site B** will be used as an ongoing example

$$C/I_{\text{ACTUAL}} = C_B - I_B$$

C = Receive signal level

I = Interference level




C/I Objective is the target criteria to satisfy a condition of non-interference

$$C/I_{\text{Objective}} = C - T + T/I$$

C = Receive level

T = Threshold

T/I = Threshold to interference value




Understanding the Frequency Coordination Process

2. Frequency Planning & Protection




Greg Macey

Manager, Microwave




FDD

Microwave systems are typically *Frequency Division Duplex* where you have **different frequencies** at each end of the path




TDD

Conversely, *Time Division Duplex* systems transmit the **same frequency** at each end but in different time slots



HI / LO FREQUENCY PLAN

- Frequency separation between transmitters and receivers (T/R split)
 - Established by industry or regulatory body
- Each site transmits in one half of the band (hi or lo) and receives in the opposite half of the band (lo or hi)
 - Alternate Hi / Lo plan in tandem paths



BUCKING = Transmit and receive on the **same side** of the frequency plan at a site



- Receiver possibly exposed to high interference level from collocated transmitter •
 - Interference calculations uncertain •
- System expansion limited at bucking site •
 - Sufficient T/R separation required •

FREQUENCY PLANNING | FREQUENCY SELECTION

Analyze against all licensed and planned systems

Identify interference-free frequencies

PREFERRED



Green = Clear by line of sight (LOS)

Yellow = Clear by terrain LOS

Red = Doesn't meet interference objective

Blue = Co-channel bucking

Freq Plan - J1		11225.0000		11265.0000		11305.0000		11345.0000		11385.0000		11425.0000		11465.0000		11505.0000		11545.0000		11585.0000		11625.0000		11665.0000	
Path #	Polarization	V	H	V	H	V	H	V	H	V	H	V	H	V	H	V	H	V	H	V	H	V	H	V	H
1	JSY - EQS	•	X			X	•																		
2	JSY - WAG	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
3	WAG - 83D	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
4	RIV - FTL									X	•	•	X												
5	JSY - 55B	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
	Polarization	V	H	V	H	V	H	V	H	V	H	V	H	V	H	V	H	V	H	V	H	V	H	V	H
Freq Plan - Q1		10735.0000		10775.0000		10815.0000		10855.0000		10895.0000		10935.0000		10975.0000		11015.0000		11055.0000		11095.0000		11135.0000		11175.0000	

FREQUENCY PLANNING | INTERFERENCE MITIGATION METHODS




**FLIP
HI-LO PLAN**



**FREQUENCY /
POLARIZATION
OFFSET**



**TERRAIN
BLOCKAGE**




**TRANSMIT
PADS OR ATPC**


RESERVED



**GROWTH CHANNEL
RELINQUISHMENT**



**ANTENNA
UPGRADES**



**DIFFERENT
FREQUENCY BAND**

Avoid Licensing Problems

WARNINGS DOCUMENT

FCC rule
& technical
compliance



ASR REPORT


Identify nearby
registered
towers (ASRs)



CALL SIGN REPORT

Match existing
FCC
call signs





1 NOTIFICATION

Notify all potentially affected parties



2 RESPONSE

Parties have 30 days to respond



3 RESOLUTION

Resolve interference concerns


Coordination Area

keyhole within 5 degrees of antenna main beam azimuth

Coordination Recipients

licensed, applied and proposed microwave and earth station systems

Frequency (GHz)	Radius (mi)	Keyhole (mi)
< 15	125	250
> 15	80	150






1

MONITOR

Analyze PCNs against existing paths



2

REPORT CASES

Notify all impacted parties



3

RESOLUTION

Resolve interference concerns

Understanding the Frequency Coordination Process

3. FCC Licensing & Management



Greg Macey
Manager, Microwave



Microwave paths **require** FCC Licensing
FCC microwave database is **site-based**



FCC FORM 601


ULS (Universal Licensing System)

Application includes **main** and up to **4 supplemental schedules**

Time to complete one FCC application is 1.25 hours

Proof of frequency coordination (supplemental showing)

Over 52,000 applications filed in last 3 years




Preparation for Filing FCC Form 601

PATH DATASHEET



APPLICATION



SUPPLEMENTAL SHOWING



LICENSE




FCC Form 601 Batch Filing Advantages




Faster!



No typographical errors



Direct data transfer from microwave database into form



Multiple FCC applications filed simultaneously

FORM 601, SCHEDULE K Completion of Construction (COC)



FINAL STEP
OF
FCC Licensing

PROVIDE
construction date
FOR EACH
path + frequency



AUTOMATIC
TERMINATION
IF NOT FILED




WARNING



PATH MUST BE **OPERATIONAL**
within **18** months
FROM **LICENSE GRANT DATE**

- 101.31 Conditional Authorization
- 101.63 Construction Period
- 101.103 Frequency Coordination Procedures
- 101.109 Maximum Allowed Bandwidth
- 101.113 Maximum EIRP
- 101.115 Antenna Standards
- 101.141 Modulation / Bit Efficiency
- 101.143 EIRP Limitations on Short Paths
- 101.145 Interference into Geostationary Satellites
- 101.147 Frequency Tables
- 1.924 Quiet Zones
- 1.929 Major versus Minor Filings



- Universal Licensing System (ULS): <https://www.fcc.gov/wireless/universal-licensing-system>
- FCC License Search: <https://wireless2.fcc.gov/UlsApp/UlsSearch/searchLicense.jsp>
- ASR Home: <https://www.fcc.gov/wireless/systems-utilities/antenna-structure-registration>
- ASR Determination: <https://wireless2.fcc.gov/UlsApp/AsrSearch/towairSearch.jsp>
- FCC Rules part 101 online: <https://www.ecfr.gov/current/title-47/chapter-I/subchapter-D/part-101?toc=1> (click parts 80-199 and then part 101)
- National Spectrum Management Association: <https://www.nsma.org/>
- Fixed Wireless Communications Coalition: <https://www.fwcc.us/index.html>
- Path Design, Frequency Coordination and Licensing: <https://www.comsearch.com/services/frequency-coordination-licensing/microwave/>

Understanding the Frequency Coordination Process

4. Comsearch Connect — Customer Portal



Greg Macey

Manager, Microwave

Protect your 6 GHz Microwave Network from Wi-Fi 6E

Comsearch can help you minimize system degradation and downtime through a 3-step process

[LEARN MORE](#)



PROJECT TRACKER



PROTECTION



PATH DATABASE



DATA PRODUCTS

COMSEARCH CONNECT | CUSTOMER PORTAL



PROJECT TRACKER

Work Orders **PCN** Filing Status PCN Renewal

Work Orders

Filter Project Engineer

18 Results ?

Project Engineer	Licensee	Description	Work Order #	Date Received	Purchase Order	Date Billed	Comsearch Engineer	Status ?
Jenny Smith	Ashburn Communications	Major Modification	292261	2023-09-14	ABD4605	2023-10-12	Rocio Palomo	In Progress
Jenny Smith	Ashburn Communications	Major Modification	292260	2023-09-13	ABD4604	2023-10-11	Michele DuVall	In Progress
Jenny Smith	Ashburn Communications	Minor - 3 Paths	292259	2023-09-12	ABD4603	2023-10-10	Dong Shin	In Progress
Jenny Smith	Ashburn Communications	Minor - 16 Paths	292258	2023-09-11	ABD4602	2023-10-09	Anh Tran	In Progress
Jenny Smith	Ashburn Communications	Minor - 19 Paths	292257	2023-09-10	ABD4601	2023-10-08	Helen Marquis	In Progress
Jenny Smith	Ashburn Communications	10 Paths - Lorton	292256	2023-09-09	ABGHJD	2023-10-07	Franco Benedict	In Progress
Jenny Smith	Ashburn Communications	9 Paths - Alexandria	292255	2023-09-08	ABGHJD	2023-10-06	Franco Benedict	In Progress
Jenny Smith	Ashburn Communications	8 Paths - Alexandria	292254	2023-09-07	ABGHJD	2023-10-05	Franco Benedict	In Progress
Jenny Smith	Ashburn Communications	Major Modification	292262	2023-09-15	ABD4606	2023-10-13	Rocio Palomo	Complete
John Doe	Ashburn Communications	Major Modification	292253	2023-09-06	ABD4597	2023-10-04	Franco Benedict	Complete
John Doe	Ashburn Communications	Major Modification	292252	2023-09-05	ABD4596	2023-10-03	Karuna Nuon	Complete
John Doe	Ashburn Communications	Major Modification	292251	2023-09-04	ABD4595	2023-10-02	Anh Tran	Complete
John Doe	Ashburn Communications	Minor - 9 Paths	292250	2023-09-03	ABD4594	2023-10-01	Karuna Nuon	Complete
John Doe	Ashburn Communications	Minor - 6 Paths	292249	2023-09-02	ABD4593	2023-09-30	Rocio Palomo	Complete
John Doe	Ashburn Communications	Minor - 14 Paths	292248	2023-09-01	ABD4592	2023-09-29	Michele DuVall	Complete

WORK ORDERS

COMSEARCH CONNECT | CUSTOMER PORTAL



PROJECT TRACKER

Work Orders **PCN** Filing Status PCN Renewal

Prior Coordination Notices

Filter Project Engineer

10 Results

Project Engineer	Licensee	# of Paths	Link Details	Job Number	Comsearch Engineer	PCN Date	Est. Clear Date	PCN Exp Date	PCN Status
John Doe	Ashburn Communications	1	☰	190514COM5AY06	Karuna Nuon	2023-04-27	2023-04-27	2023-10-27	Ready for Filing
Jenny Smith	Ashburn Communications	1	☰	190501COM5AY29	Timothy Rockett	2023-05-07	2023-05-21	2023-11-07	Ready for Filing
Jenny Smith	Ashburn Communications	2	☰	190501COM5AY19	Timothy O. Crutcher	2023-03-09	2023-03-23	2023-09-09	Ready for Filing
Jenny Smith	Ashburn Communications	1	☰	190501COM5AY18	Dong Shin	2023-03-15	2023-03-29	2023-09-15	Ready for Filing
Jenny Smith	Ashburn Communications	1	☰	190501COM5AY17	Timothy O. Crutcher	2023-04-27	2023-04-27	2023-10-27	Ready for Filing
Jenny Smith	Ashburn Communications	2	☰	190501COM5AY14	Michele DuVall	2023-05-07	2023-05-14	2023-11-07	Ready for Filing
Jenny Smith	Ashburn Communications	1	☰	190410COM5AY03	Timothy Rockett	2023-03-24	2023-04-07	2023-09-24	Ready for Filing
Jenny Smith	Ashburn Communications	1	☰	190401COM5AY02	Timothy Rockett	2023-03-15	2023-03-29	2023-09-15	Ready for Filing
Jenny Smith	Ashburn Communications	1	☰	190328COM5AY03	Timothy Rockett	2023-03-11	2023-03-24	2023-09-11	Ready for Filing
Jenny Smith	Ashburn Communications	1	☰	190410COM5AY04	Timothy Rockett	2023-03-24	2023-04-07	2023-09-24	In Progress

PCN

COMSEARCH CONNECT | CUSTOMER PORTAL



PROJECT TRACKER

Work Orders | PCN | **Filing Status** | PCN Renewal

FCC Filing Status

Filter Link ID

14 Results | Page 1 of 1

Link ID	Job #	Path Info					Site 1			Site 2	
		Band	PCN Exp. Date	Licensee	State	Call Sign	Site Name	Status	Call Sign	Site Name	Status
WORLAND-CASPER	190514COMSAY06	2.11	2023-10-27	Ashburn Communications	CA	WAX40	WORLAND	P	RX0N43	CASPER	P
EL DORADO-FIRE TOWER	190501COMSAY29	2.11	2023-11-06	Ashburn Communications	ID	WBB295	EL DORADO	P	WLAB34	FIRE TOWER	P
1370 LEVEE-ROME	190501COMSAY21	2.13	2023-09-07	Ashburn Communications	LA	WBB345	1370 LEVEE	P	WLAB84	ROME	P
FABENS PARK-REPEATER	190501COMSAY19	2.13	2023-09-08	Ashburn Communications	TX	WBB343	FABENS PARK	P	WLAB82	REPEATER	P
TOWANDA CO-CUPEY BAJO	190501COMSAY19	2.11	2023-09-08	Ashburn Communications	PA	WAX53	TOWANDA CO	G	RX0N56	CUPEY BAJO	G
DALLAS-CRYSTAL MTN	190501COMSAY18	2.11	2023-09-14	Ashburn Communications	PA	WAX52	DALLAS	G	RX0N55	CRYSTAL MTN	G
SAND HILLS-RAMBIN STOR	190501COMSAY17	2.13	2023-10-27	Ashburn Communications	TX	WBB341	SAND HILLS	G	WLAB80	RAMBIN STOR	G
ECTOR STN-POPULAR CTR	190501COMSAY14	2.13	2023-11-06	Ashburn Communications	TX	WBB338	ECTOR STN	G	WLAB77	POPULAR CTR	G
VERNAL-COEUR DALENE	190501COMSAY14	2.11	2023-11-06	Ashburn Communications	UT	WAX48	VERNAL	G	RX0N51	COEUR DALENE	G
CORNWALL-HWY59	190410COMSAY04	0.93	2023-09-23	Ashburn Communications	OR	WBB310	CORNWALL	P	WLAB49	HWY59	P
LEWIS PK-HWY 83	190410COMSAY03	0.93	2023-09-23	Ashburn Communications	WA	WBB309	LEWIS PK	G	WLAB48	HWY 83	G
QUIGGS MTN-WHITESBURG	190401COMSAY02	2.13	2023-09-14	Ashburn Communications	CA	WBB363	QUIGGS MTN	P	WLA902	WHITESBURG	P
KINGSTON RA-WARD PEAK	190328COMSAY03	2.13	2023-09-10	Ashburn Communications	NV	WBB362	KINGSTON RA	G	WLA901	WARD PEAK	G
DATA CENTER-VEGA BAJA	190320COMSAY03	2.13	2023-09-02	Ashburn Communications	CO	WBB361	DATA CENTER	G	WLA900	VEGA BAJA	G

FILING

COMSEARCH CONNECT | CUSTOMER PORTAL



PROJECT TRACKER

Work Orders | PCN | Filing Status | **PCN Renewal**

PCN Renewal

Filter Link ID

Select All (0 selected) Datasheets Export to CSV Actions

14 Results | Page 1 of 1

Path Info								Site 1			Site 2		
Link ID	Job #	Band	PCN Exp. Date	Licensee	Renewal Contact	State	Call Sign	Site Name	Status	Call Sign	Site Name	Status	Renewal Status
SAND HILLS-RAMBIN STOR	190501COMSAY17	2.13	2023-10-27	Ashburn Communications	John Doe	TX	WBB341	SAND HILLS	G	WLA880	RAMBIN STOR	G	Proposed
WORLAND-CASPER	190514COMSAY06	2.11	2023-10-27	Ashburn Communications	Jenny Smith	CA	WAX40	WORLAND	P	RXON43	CASPER	P	Proposed
EL DORADO-CENTRAL AVE	190501COMSAY11	2.11	2023-10-21	Ashburn Communications	John Doe	CA	WAX45	EL DORADO	T	RXON48	CENTRAL AVE	T	Proposed
LEWIS PK-HWY 83	190410COMSAY03	0.93	2023-09-23	Ashburn Communications	John Doe	WA	WBB309	LEWIS PK	G	WLA848	HWY 83	G	Proposed
CORNWALL-HWY59	190410COMSAY04	0.93	2023-09-23	Ashburn Communications	Jenny Smith	OR	WBB310	CORNWALL	P	WLA849	HWY59	P	Proposed
DALLAS-ITURREGUI	190410COMSAY05	0.93	2023-09-23	Ashburn Communications	John Doe	ID	WBB311	DALLAS	T	WLA850	ITURREGUI	T	Proposed
DALLAS-CRYSTAL MTN	190501COMSAY18	2.11	2023-09-14	Ashburn Communications	Jenny Smith	PA	WAX52	DALLAS	G	RXON55	CRYSTAL MTN	G	Expired
QUIGGS MTN-WHITESBURG	190401COMSAY02	2.13	2023-09-14	Ashburn Communications	John Doe	CA	WBB363	QUIGGS MTN	P	WLA902	WHITESBURG	P	Expired
ECTOR STN-REASON PEAK	190501COMSAY18	2.13	2023-09-14	Ashburn Communications	Jenny Smith	TX	WBB342	ECTOR STN	T	WLA881	REASON PEAK	T	Expired
KINGSTON RA-WARD PEAK	190328COMSAY03	2.13	2023-09-10	Ashburn Communications	Jenny Smith	NV	WBB362	KINGSTON RA	G	WLA901	WARD PEAK	G	Expired
TOWANDA CO-CUPEY BAJO	190501COMSAY19	2.11	2023-09-08	Ashburn Communications	John Doe	PA	WAX53	TOWANDA CO	G	RXON56	CUPEY BAJO	G	Expired
FABENS PARK-REPEATER	190501COMSAY19	2.13	2023-09-08	Ashburn Communications	John Doe	TX	WBB343	FABENS PARK	P	WLA882	REPEATER	P	Expired

RENEWALS

Understanding the Frequency Coordination Process

5. FCC Regulatory Updates (6GHz, 80GHz, 13GHz)



Greg Macey
Manager, Microwave

6 GHz

- FCC certifies 7 AFC providers in February 2024
- VLP device class added in Nov. 2023 (see ET Docket No. 18-295)
 - -5 dBm/MHz EIRP PSD Possibly up to 1 dBm/MHz
 - 14 dBm EIRP
- Heavily used lower and upper 6 GHz microwave licensees share with unlicensed devices

70/80 GHz

- FCC R&O and FNPRM released in January 2024
 - Allows smaller antennas (38 dBi)
 - New certification of construction requirements
 - Implements channel plans
 - De minimis modifications can keep first-in-time rights
 - Approves new aeronautical and maritime shared service
 - Future Notice for satellite earth stations

13 GHz

- FCC froze applications for new microwave sites in Sept. 2022 and Mar. 2023
- 12.7 to 13.25 GHz band proposed to be reallocated for mobile broadband use
- Current fixed links subject to relocation
- BAS may retain a small portion of the band for TV pickup / electronic news gathering



Greg Macey
Manager, Microwave
gmacey@comsearch.com

*Thank
You!*

www.comsearch.com